


Date :- 03rd June 2022



IISWBM


NOTICE INVITING TENDER

Sealed tenders are invited by IISWBM, Management House, College Square (West), Kolkata – 700 073 from authorized applicator of Berger Paints/Asian Paints/ICI Paints for repairing and painting of exterior wall of Institute Building both Administrative and Academic Block including Boundary Wall as per details given in the tender document.

Tender document with all details including terms & conditions are available from the office of the AAO during office hours on all working days from 03rd June 2022 to 13th June 2022 (Monday to Friday) between 11-00 am to 4-00 pm. You may also download tender documents from Institute's Web Site (www.iiswbm.edu). The last date of submission of sealed tender completed in all respect including all required documents by 4.00 pm on or before 15th June 2022.

Langan Indira Gupta
A. A. O. 03/06/2022

Date :- 03rd June 2022



IISWBM

NOTICE INVITING TENDER

Sealed tenders are invited by IISWBM, Management House, College Square (West), Kolkata – 700 073 from authorized applicator of Berger Paints/Asian Paints/ICI Paints for repairing and painting of exterior wall of Institute Building both Administrative and Academic Block including Boundary Wall as per details given in the tender document. Details are given below :-

Available date for Tender Documents	Submission of Tender Documents
From 03 rd June 2022 to 13 th June 2022 (Monday to Friday) between 11-00 am to 4-00 pm	By 4-00 pm on or before 15 th June 2022

Inspection date and time : 03rd June 2000 to 14th June 2022 (Monday to Friday) from 11-00 am to 4-00 pm.

Opening of Tender Documents : 16th June 2022 at 12.30 pm.

Security Deposit : 10% of the total bill amount will be deducted from the bill. Security Deposit will be released after 06 (six) month from the date of raise of final bill, if work found satisfactorily. Security Deposit shall not carry interest of any kind.

Time of Completion of Work : Within 02 months from the date of issue of work order.

Institute takes no responsibility for delay / loss or non-receipt of Tender Documents sent by post and reserves the right to reject any or all Tender without assigning any reasons whatsoever.

Application should be submitted alongwith self attested copies of following documents:-

1. Trade Licence, 2. Latest I.T. return, 3. PAN Card, 4. GST Certificate, 5. Authorization Certificate, 6. Working experience certificates etc.

Langan Ananta Gupta
A. A. O. 03/06/2022

Date :

The Director
IISWBM
College Square (west)
Kolkata:700073

Sub: Application for repairing and painting of exterior wall of Institute Building both Administrative and Academic Block including Boundary Wall as per details given in the tender document against your Advertisement in the Newspaper, Institute's Web-site / Notice Board.

Respected Sir,

In view of the above, we would like to apply for the same. Our details information is stated here under:

Name of the organization :

Address of the organization :

Trade licence No. :

PAN No. :

Latest IT Return :

GST Registration No. with rate (%) :

Authorization Certificate :

Working experience certificates :


Total Quoted Rate :

Other details if any :

Thanking you,

Yours faithfully,

(Signature with seal)



IISWBM
(Gen. Admin. Dept.)

INDIAN INSTITUTE OF SOCIAL WELFARE AND BUSINESS MANAGEMENT
MANAGEMENT HOUSE, COLLEGE SQUARE (WEST), KOLKATA – 700 073

Work Schedule for repairing and painting of exterior wall of Institute Building both Administrative and Academic Block including boundary wall

<u>Sl No.</u>	<u>Description of Work</u>	<u>Quantity</u>	<u>Rate</u> Rs. P.	<u>Amount</u> Rs. P.
01.	SPALING OF CONCRETE (specially sunshade, column, wall); Remove weak concrete corroded Rfments to be cleaned 1 st coat of SIKa RUSTOP to be applied. After 2-6 hrs 2 nd coat to be applied After 24 hrs 1-coat LP (Latex power) slurry to be applied. Put mortar (1:1.5:3) within 30 minutes. After that plastering (1:4) the surface matching with existing wall including necessary scaffolding complete in all respect.	3000 Sft.		
02.	CRACK : Civil repairing works with polymer modified mortar for cracks by cutting v-grooves, insertion of RCC block (where necessary) 600 mm c/c for stitching, sealing the crack with SIKa TOP 122 mortar, injecting cement slurry admixed with non shrink grout admixture with grout pump by placing & fixing grouting nozzle directly on the crack line @ 600/400 mm c/c, removing nozzles and mending the holes with SIKa TOP 122 mortar including necessary scaffolding complete in all respect.	1600 Rft		
03.	SALT PETRE : Remove existing plaster, cleaning with wire brush, applying a coat of Berger Damp Stop sluri after 1-2 hrs put a Sika Latex slurry (SL:W:C=1:4: 6), plastering with mortar (1:4) admixture with SLP (SLP;W=1:4) including curing, necessary scaffolding complete in all respect.	3200 Sft		
04.	DAMP WALL: Removing existing plaster, coating the walls with FOSROC Hydroproof on 3 coats with cement (as per manufacturer direction), re-plastering with mortar (1:4) admixture with SLP (SLP;W=1:4) including curing, necessary scaffolding complete in all respect.	6400 Sft.		

<u>Sl No.</u>	<u>Description of Work</u>	<u>Quantity</u>	<u>Rate</u> Rs. P.	<u>Amount</u> Rs. P.
05.	PATCH REPAIRING : Removing existing damaged plaster, re-plastering with mortar (1:4) admixture with SLP (SLP;W=1:4) including curing, necessary scaffolding complete in all respect.	2100 Sft		
06.	Applying one coat of weather coat exterior primer and two coats of weather coat long life (exterior emulsion paint, to resist chalking, flaking, fading and prevents the growth of fungus and algae) exterior paint (Berger) on masonry surface after necessary surface preparation, including scarping, cleaning, sand papering, putty work wherever necessary with scaffolding complete in all respect.	80,000 Sft.		
07.	Applying one coat of oil bound metal/wood primer, two coats of synthetic enamel paint (Hi Gloss) (Berger) on metal/wooden surface after necessary surface preparation including scrapping, cleaning & sand papering, putty work wherever necessary with scaffolding complete in all respect.	17000 Sft.		
08.	Site cleaning and removing rubbish from site to a suitable place at ground floor and transferring the same to KMC dumping ground by truck after completion of work.	1 Item		

----- X -----